



Haryana Government Gazette

Published by Authority

© Government of Haryana

No. 36-2017] CHANDIGARH, TUESDAY, SEPTEMBER 5, 2017 (BHADRA 13, 1939 SAKA)

PART-I

Notifications, Orders and Declarations by Haryana Government

HARYANA GOVERNMENT

PUBLIC WORKS DEPARTMENT

(BUILDING AND ROADS BRANCH) AMBALA CIRCLE

Notification

The 17th August, 2017

No. SE/PWD (B&R)/Ambala/CZC/17.— Decision of the Direction Committee on Haryana P.W.D. Schedule of Rates 1988 (Second Edition) held on 21/07/2017.

The Direction Committee discussed the Agenda and approved the following amendments in Haryana P.W.D. Schedule of rates 1988, Second Edition.

THESE AMENDMENTS WILL BE APPLICABLE FROM THE DATE OF GAZETTE NOTIFICATION.

Addenda and Corrigenda to the Haryana PWD Schedule of Rates 1988 (Second Edition)

A&C Slip No.19

Dated: 17/08/2017.

In the Haryana P.W.D. Schedule of Rates 1988 (Second Edition), existing items of Chapter 10 of HSR (Design Mix Cement concrete); the following amendments are made:

Existing items in HSR:

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
1.	10.64	Design Mix cement concrete of grade M-15 with minimum cement content 315 Kg/cum in foundation and plinth	Cum.	79	656.35 + CP
2.	10.65	Design Mix cement concrete of grade M-20 with minimum cement content 405 Kg/cum in foundation and plinth	Cum.	80	737.60 + CP
3.	10.66	Design Mix cement concrete of grade M-25 with minimum cement content 410 Kg/cum in foundation and plinth	Cum.	82	780.00 + CP

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
4.	10.67	Design Mix cement concrete of grade M-30 with minimum cement content 420Kg/cum in foundation and plinth	Cum.	83	790.00 + CP
5.	10.68	Design Mix cement concrete of grade M-35with minimum cement content 430Kg/cum in foundation and plinth	Cum.	85	810.00 + CP
6.	10.69	Design Mix cement concrete of grade M-40with minimum cement content 440 Kg/cum in foundation and plinth	Cum.	87	830.00 + CP
7.	10.71	Design mix cement concrete of grade M-15 with minimum cement contents 315 kg/cum in first storey upto 4 meters above plinth level.	Cum.	85.25	662.60 + CP
8.	10.72	Design mix cement concrete of grade M-20 with minimum cement contents 405 kg/cum in first storey upto 4 meters above plinth level.	Cum.	86.25	743.85 + CP
9.	10.73	Design mix cement concrete of grade M-25 with minimum cement contents 410 kg/cum in first storey upto 4 meters above plinth level.	Cum.	88.25	786.25 + CP
10.	10.74	Design mix cement concrete of grade M-30 with minimum cement contents 420 kg/cum in first storey upto 4 meters above plinth level.	Cum.	89.25	796.25 + CP
11.	10.75	Design mix cement concrete of grade M-35 with minimum cement contents 430 kg/cum in first storey upto 4 meters above plinth level.	Cum.	91.25	816.25 + CP
12.	10.76	Design mix cement concrete of grade M-40 with minimum cement contents 440 kg/cum in first storey upto 4 meters above plinth level.	Cum.	93.25	836.25 + CP

AMENDED AS UNDER:

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
1.	10.64	Design Mix cement concrete of grade M-15 with minimum cement content 240 Kg/cum in foundation and plinth	Cum.	79	580.29+ CP
2.	10.65	Design Mix cement concrete of grade M-20 with minimum cement content 300 Kg/cum in foundation and plinth	Cum.	80	633.75+ CP
3.	10.66	Design Mix cement concrete of grade M-25 with minimum cement content 300 Kg/cum in foundation and plinth	Cum.	82	668.90+ CP
4.	10.67	Design Mix cement concrete of grade M-30 with minimum cement content 320 Kg/cum in foundation and plinth	Cum.	83	688.15+ CP
5.	10.68	Design Mix cement concrete of grade M-35with minimum cement content 340 Kg/cum in foundation and plinth	Cum.	85	711.80+ CP
6.	10.69	Design Mix cement concrete of grade M-40with minimum cement content 360 Kg/cum in foundation and plinth	Cum.	87	754.18+ CP

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
7.	10.71	Design mix cement concrete of grade M-15 with minimum cement contents 240 kg/cum in first storey upto 4 meters above plinth level.	Cum.	85.25	586.54+ CP
8.	10.72	Design mix cement concrete of grade M-20 with minimum cement contents 300kg/cum in first storey upto 4 meters above plinth level.	Cum.	86.25	640.00+ CP
9.	10.73	Design mix cement concrete of grade M-25 with minimum cement contents 300 kg/cum in first storey upto 4 meters above plinth level.	Cum.	88.25	675.15+ CP
10.	10.74	Design mix cement concrete of grade M-30 with minimum cement contents 320 kg/cum in first storey upto 4 meters above plinth level.	Cum.	89.25	694.40+ CP
11.	10.75	Design mix cement concrete of grade M-35 with minimum cement contents 340 kg/cum in first storey upto 4 meters above plinth level.	Cum.	91.25	718.05+ CP
12.	10.76	Design mix cement concrete of grade M-40 with minimum cement contents 360 kg/cum in first storey upto 4 meters above plinth level.	Cum.	93.25	760.43+ CP

Note: Excess cement over the specified cement content used as per the approved Design Mix is payable separately.

K. S. SUHAG,
Convener, Central Zonal Committee,
Haryana PWD Schedule of Rates-cum-
Superintending Engineer, Ambala Circle,
PWD (B&R), Ambala Cantt.